LONDON LUTON AIRPORT

ASBESTOS PROTOCOL

London Luton Airport is committed to managing asbestos safely across the Terminal and Estate Buildings. Effective asbestos management protects employees, contractors, guests/passengers and visitors by preventing accidental disturbance of asbestos-containing materials and ensuring compliance with the Control of Asbestos Regulations 2012.

This Protocol establishes the principles for managing asbestos throughout its lifecycle, from identification and risk assessment through to maintenance, refurbishment and removal.

Our Asbestos Management Protocol is based on the following principles

Identification & Control

- Review asbestos information / Register before maintenance, projects or intrusive works.
- Complete a Refurbishment & Demolition (R&D) Survey before any intrusive maintenance, refurbishment, demolition or project works commence.
- Presume materials contain asbestos where information is unavailable.
- Prevent the accidental disturbance of asbestos-containing materials.
- Use competent asbestos surveyors and appropriately licensed or competent contractors appropriate to the work being undertaken.
- Do not introduce asbestos-containing materials into the LLA estate.

Inspection & Assurance

- Maintain an accurate and up-to-date Asbestos Register.
- Regularly inspect and monitor known asbestos-containing materials.
- Keep asbestos records, surveys and risk assessments up to date.
- Record removals, repairs and changes.
- Provide asbestos information to anyone liable to disturb asbestos-containing materials.
- Monitor compliance through inspections and audits.
- Review and continually improve asbestos management through inspections, audits and lessons learned.

This Asbestos Management Protocol provides the framework for managing asbestos across London Luton Airport. Supporting procedures, standards and work instructions define the detailed requirements for surveying, maintenance, refurbishment, removal and emergency response.

Mark Graves
Head of Technical Services
Valid Until August 2027

London Luton Airport